


# Addendum #1 (Final)



## Project Information

<b>Project Name:</b>	Linn Grove Irrigation Renovation - REBID
<b>Bid Number:</b>	F22-11-104
<b>Date:</b>	November 22, 2022
<b>Project Manager:</b>	Clint Anders

## Addendum Questions

<b>Question #1</b>	Is there somewhere on the bid documents (or will a form be provided) for us to state our: <ul style="list-style-type: none"> <li>• Intended approach to the project</li> <li>• Intended staffing levels and equipment used</li> <li>• Qualifications</li> <li>• Proposed timeframe</li> </ul>
<b>Answer</b>	The contractor should list their qualifications and experience in the bid packet., demonstrating that they can meet the CONTRACTOR QUALIFICATIONS listed in the Special Provisions. There is not attached form to include this information. Intended approach, staffing and timeframe can be included in the bid packet but is not required at this time. This can be discussed in greater detail during interviews and when finalizing the contract.
<b>Question #2</b>	Please confirm that sod will be used for trench restoration
<b>Answer</b>	Yes, sod will be required
<b>Question #3</b>	Is there a requirement to continuously staff the project one construction begins?
<b>Answer</b>	The contractor will be responsible for a keeping a safe, clean fully operational site during construction. The approach to the scope of work, including timing and staffing of construction, can be discussed during interviews and after award.
<b>Question #4</b>	Does the HDPE indicated need to be sleeved or will it be direct buried?
<b>Answer</b>	HDPE pipe will not require sleeving.
<b>Question #5</b>	What size is P.O.C. 1?
<b>Answer</b>	The size and pressure was unable to be verify at the time of design. Volume is stated on the plans.