Addendum #1



	Project Information
Project Name:	Highland Hills Pump Station Control Panel Procurement
Bid Number:	F24-01-011
Date:	March 25, 2024
Project Manager:	Ryan Duve
	Change Description
Change #1	Add Exhibit 6 " HIGHLAND HILLS GOLF COURSE IRRIGATION PUMP STATION IMPROVEMENTS PROJECT" plans.
Explanation	This is For Your Information only: Exhibit 6 shows the current location of the control panel and also the proposed location of the replacement control panel.
Change #2	Add Exhibit 7 " Flowtronex PSI Ltd Automatic Vertical Turbine Variable Speed Prefabricated Pump Station Technical Specification"
Explanation	This is For Your Information only: Exhibit 7 provides information on the existing pumps that the replacement control panel will control.
Change #3	Change the RFP's Schedule of Events Proposal Due Date from "April 2, 2024, by 12:00" PM to "April 3, 2024, by 12:00 PM"
Explanation	Change provides Vendors an additional day to prepare and submit proposals.
Change #4	Change the RFP's Section I. Background, Overview, and Goals, Paragraph B. Minimum Mandatory Qualifications of Offeror by deleting the paragraph in its entirety and replacing with the following, "Qualified vendors shall be limited to manufacturers that can meet requirements within Exhibit 5."
Explanation	Change allows other Vendors to submit a proposal to this RFP.
Change #5	Change Exhibit 5, 2.3 B. by inserting the following, "4. Or approved equal."
Explanation	Change allows other Vendors to submit a proposal to this RFP.

	1. There are two Amiad filter controls mounted onto the existing control panel. We will want the
	NEW filter controls integrated into the panel.
	2. There is an existing RTU for SCADA. We want NEW SCADA communication integrated into the
	panel.
Additional	3.Panel manufacturers supply the 10" mag meter.
Information	4.Control panel shall have a minimum 2-year warranty.
	5. The new control panel should be equipped with legs. The height of the building is 7'-6". The clear
	height of the double doors is 6'-7". Assume that the panel will need to fit through the door, not while
	the roof is being replaced as part of pump station improvements project.

EXHIBIT 6

RFQ # F23-04-034, WORK ORDER NO. 1 **NON-POTABLE IRRIGATION** INFRASTRUCTURE **ON-CALL PRIME CONTRACTORS**

CITY OF GREELEY HIGHLAND HILLS GOLF COURSE **IRRIGATION PUMP STATION IMPROVEMENTS** PROJECT



PROJECT LOCATION



SHEET INDEX

TITLE SHEET SHEET 1 - EXISTING CONDITIONS (PLAN VIEWS) SHEET 2 - EXISTING CONDITIONS (PROFILE VIEWS) SHEET 3 - DEMOLITION SHEET 4 - PROPOSED IMPROVEMENTS SHEET 5 - DETAILS





PLAN VIEW WITHOUT PIPING INSIDE DIMENSIONS

ITEM NO.	ITEM DESCRIPTION	NOTES	ITEM NO.	ITEM DESCRIPTION	NOTES	ITEM NO.	ITEM DESCRIPTION	NOTES
	PRECAST CONCRETE BUILDING W/CONCRETE							
1	ROOF	ROOF HAS TWO SECTIONS. SEAM LEAKS.	9	RTU ANTENNA		17	PRESSURE RELIEF VALVE (PRV)	
2	ELECTRICAL SERVICE EQUIPMENT		10	12" DISHARGE PIPE		18	75 HP PUMP MOTOR (TYP OF 3)	
							6" PUMP DISCHARGE PIPING, ISOLATION VALVE,	
3	120 V LIGHTING PANEL		11	4" FILTER WASTE PIPE		19	AND CHECK VALVE	
							2" PRESSURE MAINTENANCE PUMP PIING,	
4	XCEL'S CT PANEL		12	UNIT HEATER		20	ISOLATION VALVE, AND CHECK VALVE	
5	ELECTRICAL DISCONNECT		13	AMIAD FILTRATION SYSTEM AND PIPING		21	10" DISCHARGE PIPING TO FILTER EQUIPMENT	CENTER LINE ONLY SHOWN
					CONTROL PANEL MOUNTED ON TOP OF			
6	VENTILATION LOOVER		14	PUMP SKID	SKID	22	PRECAST CONCRETE ROOF	ROOF HAS TWO SECTIONS. SEAM LEAKS.
				10" BUTTERFLY VALVE WITH				
7	EXHAUST FAN		15	HANDWHEEL/ACTUATOR				
8	REMOTE TELEMETRY UNIT (RTU)		16	14" PUMP DISCHARGE HEADER	WELDED STEEL AND FITTINGS			

PLAN VIEW WITH SKID PIPING DETAIL



ITEM NO.	ITEM DESCRIPTION	NOTES	ITEM NO.	ITEM DESCRIPTION	NOTES	ITEM NO.	ITEM DESCRIPTION
	PRECAST CONCRETE BUILDING W/CONCRETE						
1	ROOF	ROOF HAS TWO SECTIONS. SEAM LEAKS.	9	RTU ANTENNA		17	PRESSURE RELIEF VALVE (PRV)
2	ELECTRICAL SERVICE EQUIPMENT		10	12" DISHARGE PIPE		18	75 HP PUMP MOTOR (TYP OF 3)
							6" PUMP DISCHARGE PIPING, ISO
3	120 V LIGHTING PANEL		11	4" FILTER WASTE PIPE		19	VALVE, AND CHECK VALVE
							2" PRESSURE MAINTENANCE PUN
4	XCEL'S CT PANEL		12	UNIT HEATER		20	ISOLATION VALVE, AND CHECK VA
5	ELECTRICAL DISCONNECT		13	AMIAD FILTRATION SYSTEM AND PIPING		21	10" DISCHARGE PIPING TO FILTER
					CONTROL PANEL MOUNTED ON TOP OF		
6	VENTILATION LOOVER		14	PUMP SKID	SKID	22	PRECAST CONCRETE ROOF
				10" BUTTERFLY VALVE WITH			
7	EXHAUST FAN		15	HANDWHEEL/ACTUATOR		23	PUMP EQUIPMENT HATCH
8	REMOTE TELEMETRY UNIT (RTU)		16	14" PUMP DISCHARGE HEADER	WELDED STEEL AND FITTINGS		
	1 2 3 4 5 6 7 8	ITEM NO. ITEM DESCRIPTION PRECAST CONCRETE BUILDING W/CONCRETE 1 ROOF 2 ELECTRICAL SERVICE EQUIPMENT 3 120 V LIGHTING PANEL 4 XCEL'S CT PANEL 5 ELECTRICAL DISCONNECT 6 VENTILATION LOOVER 7 EXHAUST FAN 8 REMOTE TELEMETRY UNIT (RTU)	ITEM NO. ITEM DESCRIPTION NOTES PRECAST CONCRETE BUILDING W/CONCRETE ROOF HAS TWO SECTIONS. SEAM LEAKS. 2 ELECTRICAL SERVICE EQUIPMENT 3 120 V LIGHTING PANEL 4 XCEL'S CT PANEL 5 ELECTRICAL DISCONNECT 6 VENTILATION LOOVER 7 EXHAUST FAN 8 REMOTE TELEMETRY UNIT (RTU)	ITEM NO. ITEM DESCRIPTION NOTES ITEM NO. PRECAST CONCRETE BUILDING W/CONCRETE ROOF HAS TWO SECTIONS. SEAM LEAKS. 9 1 ROOF ROOF HAS TWO SECTIONS. SEAM LEAKS. 9 2 ELECTRICAL SERVICE EQUIPMENT 10 3 120 V LIGHTING PANEL 11 4 XCEL'S CT PANEL 12 5 ELECTRICAL DISCONNECT 13 6 VENTILATION LOOVER 14 7 EXHAUST FAN 15 8 REMOTE TELEMETRY UNIT (RTU) 16	ITEM NO.ITEM DESCRIPTIONNOTESITEM NO.ITEM DESCRIPTIONPRECAST CONCRETE BUILDING W/CONCRETE ROOFROOF HAS TWO SECTIONS. SEAM LEAKS.9RTU ANTENNA2ELECTRICAL SERVICE EQUIPMENT1012" DISHARGE PIPE3120 V LIGHTING PANEL114" FILTER WASTE PIPE4XCEL'S CT PANEL12UNIT HEATER5ELECTRICAL DISCONNECT13AMIAD FILTRATION SYSTEM AND PIPING6VENTILATION LOOVER14PUMP SKID7EXHAUST FAN15HANDWHEEL/ACTUATOR8REMOTE TELEMETRY UNIT (RTU)101614" PUMP DISCHARGE HEADER	ITEM NO. ITEM DESCRIPTION NOTES ITEM NO. ITEM DESCRIPTION NOTES PRECAST CONCRETE BUILDING W/CONCRETE ROOF ROOF HAS TWO SECTIONS. SEAM LEAKS. 9 RTU ANTENNA	ITEM NO. ITEM DESCRIPTION NOTES ITEM NO. ITEM DESCRIPTION NOTES ITEM NO. PRECAST CONCRETE BUILDING W/CONCRETE PRECAST CONCRETE BUILDING W/CONCRETE ROOF ROOF HAS TWO SECTIONS. SEAM LEAKS. 9 RTU ANTENNA 17 2 ELECTRICAL SERVICE EQUIPMENT 10 12" DISHARGE PIPE 18 18 3 120 V LIGHTING PANEL 11 4" FILTER WASTE PIPE 19 19 4 XCEL'S CT PANEL 11 4" FILTER WASTE PIPE 20 19 4 XCEL'S CT PANEL 12 UNIT HEATER 20 21 5 ELECTRICAL DISCONNECT 13 AMIAD FILTRATION SYSTEM AND PIPING 20 6 VENTILATION LOOVER 14 PUMP SKID SKID 22 7 EXHAUST FAN 15 HANDWHEEL/ACTUATOR 23 23 8 REMOTE TELEMETRY UNIT (RTU) 16 15 HANDWHEEL/ACTUATOR 23



ITEM NO.	ITEM DESCRIPTION	NOTES	ITEM NO.	ITEM DESCRIPTION	NOTES
1	CONTROL PANEL	REMOVE AND DISPOSE.	6	EXHAUST FAN	REMOVE AND DISPOSE.
2	PRV	REMOVE AND DELIVER TO COG.	7	ELECTRICAL SERVICE EQUIPMENT	REMOVE AND DISPOSE.
		REMOVE AND DISPOSE. REUSE PIPE			
3	DISCHARGE PIPING AND VALVES	SUPPORTS IF POSSIBLE.	8	LIGHTS AND ELECTRICAL CONDUITS MOUNTED TO ROOF	REMOVE AND DISPOSE.
4	PUMP SKID	REFURBISH BY BLASTING AND PAINTING.	9	CONCRETE ROOF PANELS AND EQUIPMENT HATCH	REMOVE AND DISPOSE.
5	VENTILATION LOOVER	REMOVE AND DISPOSE.			



LOCATION (PLAN VIEW)

о.	ITEM DESCRIPTION	NOTES	
	NEW 2" CHECK VALVE AND BALL VALVE ASSEMBLY	SERVES SUBMERSIBLE PRESSURE MAINT. PUMP	
	10" MAG METER	FURNISHED BY OTHERS	
	10" DIAM. X 22" STEEL SPOOL (FL X PE)	CONFIRM LENGTH	
	10" FLANGED COUPLING ADAPTER		
	NEW 10" WAFER BUTTERFLY VALVE W/HANDWHEEL ACTUATOR		
	LOUVERS (TYP OF 3)		
	EXHAUST FANS (TYP OF 2)		
	PUMP CONTROL PANEL	BY CITY'S ELECTRICAL CONTRACTOR	
	NEW RTU ANTENNA	BY CITY'S ELECTRICAL CONTRACTOR	
	NEW BUILDING ELECTRICAL SERVICE SYSTEM	BY CITY'S ELECTRICAL CONTRACTOR	



4" PRESSURE RELIEF/SURGE ANTICIPATION SYSTEM

_				
	ITEM NO.	ITEM DESCRIPTION	NOTES	
	1	EXISTING PUMP SKID		
	2	EXISTING PUMP DISCHARGE HEAD		
	3	NEW PUMP DISCHARGE HEADER SUPPORTS		
	4	NEW 10" DIAM. STEEL PUMP DISCHARGE HEADER		
	5	NEW 4" BUTTERFLY VALVE WITH LEVER ACTUATOR	ITEM 5 ISOLATION VALVE	
	6	NEW 4" PRESSURE RELIEF/ANTICIPATION PIPING		
	7	NEW 4" BUTTERFLY VALVE WITH ELECTRIC ACTUATOR	SUPPLIED BY PUMP CONTROLS MANUFACTURER/REP	

SHEET 5

EXHIBIT 7

FLOWTRONEX PSI Ltd

Automatic Vertical Turbine Variable Speed Prefabricated Pump Station Technical Specification

Project Name: Highland Hills Golf Course	March 18, 1997
Project Location: Greeley, Colorado	

Pumping System Model No. Total Design Criteria: Total Design Flow: FPX- VWTP-2000-4-115 Quantity of Pumps: 4 2000 GPM @ 115 psi

Motor and Pump Data:	PM Pump	Pump#1	Pump#2	Pump#3
Motor Spec Motor h.p.	5	75	75	75
Motor rpm	1800	1800	1800	1800
Motor service factor	1.15	1.15	1.15	1.15
Motor efficiency	84%	91%	91%	9.1%
Motor power factor	85	87	87	87
Motor type	SUB	WP1	WP1	WP1
Motor disconnect volts	600	600	600	600
Motor FLA rating, amps	7.6	96	96	96
Motor fuse amps	10	125	125	125
Motor fuse AIC rating	200,000	200,000	200,000	200,000
Motor IEC starter size	12	110	100	100
Motor O.L. rating, amps	7.6	96	96	96
Motor cfm requirements	80	1200	1200	1200
Total cfm requirements				3,680
Pump Spec Pump gpm	45	667	667	667
Pump efficiency at design	65%	83.85%	83.85%	83.85%
Pump shut off head	430	375	375	375
Pump column pipe id	2"	8"	8"	8"
Pump shaft od	n/a	1.25"	1.25"	1.25"
Pump discharge size	2"	8"	8	8"
Pump check valve size	2	8"	8"	8"
Pump check rating, psi	200	200	200	200
Pump check psi drop at capacity	.75	1	1	1
Pump discharge isolation valve size	2	8"	8"	8"
Pump disch. isolation valve rating, psi	200	200	200	200

2,000 gpm

Motor Starting Code G, Class F Insulation,

Minimum water coverage as measured from eye of bottom impeller: 24"

Service Entrance; 297 amps, 200,000 Fault Amps, 237 KVA, 460 volts, 3 phase, 60 HZ Main Disconnect: 600 Volts, 400 amps

Starting Equipment - U.L. Listed as Industrial Control Assembly: Controls U.L. Listed as Industrial Control Assembly. VFD Controls U.L. Listed as Industrial Control Assembly:

Perating Temp: 0 to 40 °C (32 - 104 °F) Humidity: 5-95% Non-condensing Minimum Efficiency (full load, base speed) 98%

Input Voltage: 3 phase, 480 Volts AC

Input frequency:50/60 hzOutput Voltage:3 phase, 0 - 480 Volts ACrequency Rating:100% continuous drive rating, Intermittent111% Drive rating for one minute.

Phase Failure and low voltage shutoff at 90% of motor name plate voltage on all three legs 83% on one leg for five seconds.

Low discharge pressure shutdown at 105 psi after all pumps are running for 60 seconds continuously. High discharge pressure shutdown at 125 psi after all pumps are running for 60 seconds continuously. Low water level safety shutdown if water falls to within two feet of pump suction.

Relief Valve Size: 6"	
Pressure Rating:	175 psi
Pilot Setting:	160 psi

Flow sensor Brass, Pressure rating: 400 psi

System Isolation Valve: 8"

Pressure rating: 200 psi

LS-32 with 21" SDR



DIMENSIONS AND WEIGHTS

MODELNO.	HP	LENGTH (INCHES)	WIDTH · (INCHES)	APPROX. UNIT SHIPPING WT. (LBS.)
40S10-3	9 12 9	25 5/8	3 15/13	32
40S15-5	1 1/2	30 1/2	3 15/16	37
40S20-7	2	33	3 15/15	41
40S30-9	3	43 3/8	3 15/16	65
40S50-12	5	51 ½	3 15/16 .	78
40S50-15	5	56 ½	3 15/16	84
40S75-21	7 1/2*	74 1/2	3 15/16	120
40975.2F	716*	91 1/3	0.15%	124
40S100-30	10*	103 1/2	3 15/15	181

th motor is provided as standard for bidels.

fications are subject to change without

Deep Set models for higher head.

