

Addendum #1



Capital Project Committee

Project Information

Project Name:	2020 Concrete Repair
Bid Number:	RFP #FD20-05-093
Date:	June 2, 2020
Manager:	Rick Dorsey

Addendum Items

Item 1	<p>Due to the corona-virus, the City is requiring the following for submitting bids and the opening of bids:</p> <p>see attached instructions for submittal of bid responses</p> <p>See below for Bid Opening Instructions</p> <p>Doug Clapp is inviting you to a scheduled Zoom meeting.</p> <p>Join Zoom Meeting</p> <p>https://greeleygov.zoom.us/j/97806512796</p> <p>Meeting ID: 978 0651 2796</p> <p>Password: 878441</p> <p>Dial by your location</p> <ul style="list-style-type: none">+1 253 215 8782 US (Tacoma)+1 346 248 7799 US (Houston)
Item 2	<p>The excel bid schedule quantities are carried out to multiple decimal places and as a result may not match the extended pricing as shown on the rounded numbers in the project manual bid tab.</p> <p>Do you want the bids to reflect the units on the excel bid tab or the units in the project manual bid tab? Bid Item Quantities (not dollar amounts) should be rounded to the nearest whole number. I have attached an updated xls with whole numbers in the quantities column, if you want to attach it.</p>
Item 3	<p>The bid schedule shows item 29, Stamped Concrete (Add On) unit to be "CY". However the measurement and payment section of the project manual shows the unit to be "SY". SY is typical for stamped concrete. Please clarify. Stamped Concrete is in fact measured in SY (square yards). Please see revised Bid Tab.</p>

Item 4	Bid Item 29, Stamped Concrete (Add On) bid schedule unit is CY, but project manual calls out SY. Typical is SY. Unit of measure for Bid Item 29 is SY. (Also corrected in revised Bid tab)
Item 5	What pay item should the two inlet removals be covered under? I suggest that they be included in Item 32, Remove 6" CMP. Change bid item 32: Remove 6" CMP (19th Ave & 25th St) description to – Remove 6" corrugated metal pipe 0-2 foot depth including 2 "bubbler" inlets at the ends of the CMP run.
Item 6	Section 00620 - Special Provisions, Item 4, Contract Time & Scheduling states "All streets will remain open to traffic". I request that street closures be allowed with PM's approval. Change wording to: Street closures will be allowed with COG Traffic Engineer and PM's approval.

Bid Responses will only be accepted electronically during the COVID-19 event.

Instructions for electronic submittal.

Email your Bid Response to purchasing@greeleygov.com. Submit your Bid response to this email only – please do not email to multiple people. Only email's sent to purchasing@greeleygov.com will be considered as responsive to the invitation to bid. Emails sent to other City emails may be considered as non-responsive and may not be reviewed.

Bids shall be submitted in a single Microsoft Word or PDF file under 20MB

The Bid number and Project name **must be noted** in the subject line, otherwise the Bid may be considered as non-responsive to the Bid.

Electronic submittals will be held, un-opened, until the time and date noted in the Bid documents or posted addenda.

Section 00130 - Bid Schedule

2020 Concrete Repair Program

Item #	Description	Unit	Bid	Unit	TOTAL COST
			Quantity	Bid Price	
1	Remove Curb & Gutter (0 to 2' Pan)	LF	5,368		\$ -
2	Remove Concrete Flatwork - Thickness Varies	SY	2,740		\$ -
3	Removal of Rollover C&G/Sidewalk	LF	3,070		\$ -
4	Remove Asphalt (Thickness Varies)	SY	981		\$ -
5	Sawcut Joint	LF	400		\$ -
6	Concrete Sawcut Demo	LF	210		\$ -
7	New C&G 0-2' Pan (i.e. Vertical Curb and Gutter: Sim to S-16)	LF	4,555		\$ -
8	New High Back Curb and Gutter (8" and above)	LF	1,000		\$ -
9	24 Hour High Early Mix - Up Charge	CY	100		\$ -
10	New Rollover C&G and SW	LF	3,070		\$ -
11	New 4" Concrete	SY	349		\$ -
12	New 6" Concrete	SY	807		\$ -
13	New 8" Concrete	SY	1,626		\$ -
14	New 5" Concrete w/ Fiber Reinforcement	SY	478		\$ -
15	Unclassified Excavation	CY	75		\$ -
16	Compacted Stabilization Subgrade Import (6" Base)	TON	215		\$ -
17	Major Re-landscaping (Sprinklers, etc.)	HR	36		\$ -
18	Reconstruct Inlet Top (up to 2' below grade)	EA	5		\$ -
19	Adjust Meter Pit	EA	11		\$ -
20	Landscape Curb 0-6"	LF	580		\$ -
21	Landscape Curb 7-18"	LF	200		\$ -
22	Landscape Curb 19-48"	LF	150		\$ -
23	ADA Detectable Warning plates/domes	SF	472		\$ -
24	Chase Drain (12" max opening)	SF	36		\$ -
25	Remove and Reset mailbox	EA	5		\$ -
26	Tree and Root Pruning	HR	9		\$ -
27	Saw Cut to Preserve Asphalt	LF	255		\$ -
28	Colored Concrete (4 LB Max.) (Add On)	CY	75		\$ -
29	Stamped Concrete (Add On)	SY	75		\$ -
30	Portable Sanitary Station	LS	1		\$ -
31	4" PVC Installed Under Sidewalk	LF	100		\$ -
32	Remove 6" CMP (19th Ave & 25th St)	LF	75		\$ -
33	Arrow Board	Day	54		\$ -
34	Certified Flagger (When Directed By City)	Hour	80		\$ -
35	Quality Control - Standard Proctor	EA	14		\$ -
36	Quality Control - Soils Compaction	EA	15		\$ -
37	Quality Control - Concrete Test & Break Results	EA	17		\$ -
Total					\$ -

Vendor Name: _____

Authorized Signature: _____

Print Name: _____

Phone Number: _____ Fax Number: _____

Email Address: _____ Date: _____