

Addendum #2



Capital Project Committee

Project Information

Project Name:	Centerplace Turn Lane Improvement - Phase II
Bid Number:	FD21-01-003
Date:	January 25, 2021
Project Manager:	Brian Ward

Addendum Items

Item 1	What amounts are to be input into the two Force Accounts? See revised bid tab sheet.
	Please see attached revised Bid Tab Sheet

CENTERPLACE TURN LANE IMPROVEMENTS PROJECT PHASE II - BID TAB

City of Greeley

CONTRACT ITEM NO.	CONTRACT ITEM	UNIT	Phase II	ITEM COST	TOTAL COST
1010	Mobilization	LS	1		\$ -
1010	Construction Surveying	LS	1		\$ -
1010	Construction Traffic Control	LS	1		\$ -
2000	Reset Ground Sign	EA	1		\$ -
2000	Reset Street Name Sign Panel	EA	1		\$ -
2000	Reset Fire Preemption Unit	EA	1		\$ -
2000	Reset Intersection Detection System (Camera)	EA	1		\$ -
2000	Reset Street Light	EA	1		\$ -
2000	Landscape and Irrigation Remediation	SF	2,960		\$ -
2220	Clearing and Grubbing	LS	1		\$ -
2220	Removal of Concrete Pavement	SY	200		\$ -
2220	Removal of Asphalt Mat	SY	140		\$ -
2220	Removal of Curb and Gutter	LF	319		\$ -
2220	Removal of Sidewalk	SY	290		\$ -
2220	Removal of Concrete Curb Ramp	EA	2		\$ -
2220	Removal of Asphalt Mat (Planing)	SY	145		\$ -
2220	Removal of Traffic Signal Equipment	EA	1		\$ -
2220	Removal of Fire Hydrant	EA	1		\$ -
2220	Removal of Inlet	EA	1		\$ -
2223	Structure Backfill (Flow-Fill)	CY	25		\$ -
2225	Unclassified Excavation (Complete in Place)	CY	360		\$ -
2227	Subgrade Preparation (12 Inch Depth)	SY	1,025		\$ -
2229	Aggregate Base Course (Class 6)	TON	156		\$ -
2575	Hot Mix Asphalt (Grading S) (75) (PG 64-22)	TON	30		\$ -
2575	Hot Mix Asphalt (Grading S) (75) (PG 76-28)	TON	44		\$ -
2576	Hot Mix Asphalt (Patching)	TON	30		\$ -
2585	Concrete Pavement (7.5 Inch)	SY	242		\$ -
2603	18 Inch RCP (CIP)	LF	10		\$ -
2604	Double Combination Inlet Type 3	EA	1		\$ -
2610	Modify Manhole	EA	1		\$ -
2610	Adjust Pullbox to Grade	EA	1		\$ -
2618	Pavement Markings	SF	241		\$ -
2618	Pavement Markings (Words and Symbols)	SF	31		\$ -
2618	Pavement Markings (Xwalk)	SF	512		\$ -
2618	Sign Panel (Class I)	SF	26		\$ -
2618	Steel Sign Post	EA	2		\$ -
2618	Sign Anchor	EA	2		\$ -
2810	Concrete Washout Structure	EA	1		\$ -
2810	Inlet Protection	EA	1		\$ -
2810	Construction Fence (Plastic)	LF	309		\$ -
2810	Erosion Control Maintenance	LS	1		\$ -
2810	Topsoil (4" Depth)	CY	26		\$ -
3310	Concrete Curb Ramp	SY	27		\$ -
3310	Concrete Sidewalk (6 Inch)	SY	306		\$ -
3310	6" Vertical Curb and Gutter (Median, Spill)	LF	20		\$ -
3310	6" Vertical Curb and Gutter (Catch)	LF	260		\$ -
3310	Median Cover (Patterned Concrete)	SY	8		\$ -
3310	Concrete Crossspan (6 Inch)	SY	98		\$ -
5030	Drilled Caisson (18 Inch)	LF	12		\$ -
5030	Drilled Caisson (36 Inch)	LF	12		\$ -
6130	2 Inch Electrical Conduit (Plastic)	LF	100		\$ -
6130	3 Inch Electrical Conduit (Plastic)	LF	100		\$ -
6130	Pull Box (16"x24"x12")	EA	1		\$ -
6130	Wiring	LS	1		\$ -
6130	Luminaire (LED)	EA	1		\$ -
6140	Pedestrian Signal Face (16) (Countdown)	EA	2		\$ -
6140	Traffic Signal Face (12-12-12)	EA	2		\$ -
6140	Traffic Signal Face (12-12-12-12-12)	EA	1		\$ -
6140	Signal Head Backplate	EA	1		\$ -
6140	Pedestrian Push Button	EA	4		\$ -
6140	Traffic Signal-Light Pole Steel (1-30 Foot Mast Arm)	EA	1		\$ -
6140	Traffic Signal Pedestal Pole Steel	EA	1		\$ -
6140	Pedestal Pole (3 Foot 6 Inch)	EA	2		\$ -
6190	Fire Hydrant Assembly	EA	1		\$ -
7000	F/A Minor Contract Revisions	F/A	1	\$ 15,000.00	\$ 15,000
7000	F/A Erosion Control	F/A	1	\$ 5,000.00	\$ 5,000
			TOTAL		

Total Bid (written out):

Vendor Name:

Authorized Signature:

Print Name:

Phone Number:

Fax Number:

Email Address:

Date: