

# Addendum #2



## Capital Project Committee

### Project Information

Project Name:	Greeley Fishing Pond Remedial Action Plan Implementation & Vegetative Soil Cover Construction
Bid Number:	FL20-01-001
Date:	December 12, 2019
Project Manager:	Brian Ward

### Addendum Items

<b>Item 1:</b>	A revised bid tab has been included. This bid tab will be used for evaluation of the cost of efforts for the project.
<b>Item 2:</b>	The quality control sampling of all imported soils for the project shall be the responsibility of the contractor. Documentation must be supplied to the City that all imported soils meet the project specifications in accordance with CDPHE reporting requirements. Certification from the soil source, such as a gravel pit, may be used if allowed by CDPHE reporting requirements. No onsite soils may be used as part of this project.
<b>Item 3:</b>	A project specific RACS Management Plan will not be required for the contractors abatement company to supply. If a Project Specific RACS Management Plan is required the City will supply this item to the contractor at no cost to the contractor.
<b>Item 4:</b>	All equipment and labor associated with crushing of the concrete on site shall be supplied by the contractor and included in the cost proposal for the project. The contractor shall also supply all permits associated with the crushing operations as part of the cost proposal for the project.
<b>Item 5:</b>	All tress / wood on the site which are dead and / or on the ground are considered rubbish and will be removed as part of Item 4a - Clearing and Grubbing. These trees do not count as part of item 4c - Live Tree Removal.
<b>Item 6:</b>	1 piece of laminate tile, approximately 12" in length x 6" in width has been identified as friable asbestos and will have to removed from the site. The contractor will include removal of this piece of asbestos into item 11a - Selective Pick of Asbestos Containing Concrete.
<b>Item 7:</b>	Chipping from onsite tree removal may be disposed of at a location to be determined on the 39 acre site.
<b>Item 8:</b>	The City may, at their discretion, remove items it desires to reuse such as gates, fence posts, etc. Any item on site at the beginning of construction is considered part of the project and must be disposed of, as appropriate, at the cost of the contractor.