

Addendum #2



Capital Project Committee

Project Information

Project Name:	Sheep Draw Trail at 83rd Avenue
Bid Number:	FD21-03-063
Date:	April 12, 2021
Project Manager:	Tom Hellen

Addendum Items

Item 1	See below for Bid Opening Instructions - Wednesday, April 14, 2020 at 2:00pm
	Join Zoom Meeting
	https://greeleygov.zoom.us/j/82644753082
	Meeting ID: 826 4475 3082
	Passcode: 999999
	Dial by your location
	+1 312 626 6799 US (Chicago)
	+1 346 248 7799 US (Houston)
	+1 669 900 6833 US (San Jose)
Item 2	Item 32 on the bid tab has been revised concerning hot mix asphalt quantity
	see attached revised bid tab.

BASE BID TAB SHEET



PROJECT: Sheep Draw Trail At 83rd Avenue
PROJECT DESCRIPTION: Base Bid Quantities
City of Greeley

Item No.	CDOT #	Item	Unit	Quantity	Bid Price	Cost
1	201-00000	CLEARING AND GRUBBING	LS	1		\$0.00
2	201-00005	REMOVAL OF DEBRIS	LS	1		\$0.00
3	202-00010	REMOVAL OF TREE	EA	9		\$0.00
4	202-00027	REMOVAL OF RIPRAP	SY	35		\$0.00
5	202-00035	REMOVAL OF PIPE	LF	80		\$0.00
6	202-00090	REMOVAL OF DELINEATOR	EA	2		\$0.00
7	202-00200	REMOVAL OF SIDEWALK	SY	106		\$0.00
8	202-00203	REMOVAL OF CURB & GUTTER	LF	10		\$0.00
9	202-00220	REMOVAL OF ASPHALT MAT	SY	157		\$0.00
10	202-	REMOVAL OF MAILBOX	EA	1		\$0.00
11	202-02000	REMOVAL OF FENCE	LF	130		\$0.00
12	202-02035	REMOVAL OF GATE	EA	2		\$0.00
13	202-05006	SAWING CONCRETE (6 INCH)	LF	10		\$0.00
14	202-05030	SAWING ASPHALT (10 INCH)	LF	205		\$0.00
15	203-00000	UNCLASSIFIED EXCAVATION	CY	76		\$0.00
16	203-00100	MUCK EXCAVATION	CY	638		\$0.00
17	206-00100	STRUCTURE BACKFILL CLASS 1	CY	82		\$0.00
18	207-00210	STOCKPILE TOPSOIL	CY	285		\$0.00
19	208-00007	EROSION LOG (8 INCH)	LF	1660		\$0.00
20	208-00035	AGGREGATE BAG	LF	8		\$0.00
21	208-00045	CONCRETE WASHOUT STRUCTURE	EA	1		\$0.00
22	208-00050	STORM DRAIN INLET PROTECTION	EA	2		\$0.00
23	208-00070	VEHICLE TRACKING PAD	EA	1		\$0.00
24	208-00207	EROSION CONTROL MANAGEMENT	DAY	10		\$0.00
25	210-00010	RESET MAILBOX STRUCTURE	EA	2		\$0.00
26	212-00006	RESET FENCE	LF	175		\$0.00
27	212-00028	SEEDING (NATIVE)	ACRE	0.48		\$0.00
28	212-00201	SEEDING (WETLANDS)	ACRE	0.05		\$0.00
29	216-00201	SOIL RETENTION BLANKET (STRAW-COCONUT) (BIODEGRADABLE CLASS 1)	SY	2562		\$0.00
30	304-06000	AGGREGATE BASE COURSE (CLASS 6)	TON	594		\$0.00
31	403-00720	HOT MIX ASPHALT (PATCHING)	TON	10		\$0.00
32	403-34741	HOT MIX ASPHALT (GRADING SX) (75)(PG 64-22)	TON	8		\$0.00
33	506-00212	RIPRAP (12 INCH)	CY	412		\$0.00
34	601-03050	CONCRETE CLASS D (WALL)	CY	19		\$0.00
35	602-00000	REINFORCING STEEL	LB	765		\$0.00
36	603-01180	18 INCH REINFORCED CONCRETE PIPE	LF	35		\$0.00
37	603-05018	18 INCH REINFORCED CONCRETE END SECTION	LF	4		\$0.00
38	603-70703	7X3 FOOT CONCRETE BOX CULVERT (PRECAST)	LF	60		\$0.00
39	607-60116	16 FOOT GATE	EA	1		\$0.00
40	608-00025	CONCRETE BIKEWAY (5 INCH)	SY	1215		\$0.00
41	608-00350	CONCRETE SIDEWALK (COLORED/PATTERED) (5 INCH)	SY	145		\$0.00
42	609-21020	CURB AND GUTTER TYPE 2 (SECTION II-B)	LF	80		\$0.00
43	612-00001	DELINEATOR TYPE 1	EA	3		\$0.00
44	614-00011	SIGN PANEL (CLASS 1)	SF	11		\$0.00
45	614-00214	STEEL SIGN POST (1.75X1.75 TUBING)	LF	40		\$0.00
46	620-00020	SANITARY FACILITY	EA	1		\$0.00
47	625-00000	CONSTRUCTION SURVEYING	LS	1		\$0.00
48	626-00000	MOBILIZATION	LS	1		\$0.00
49	627-00004	EPOXY PAVEMENT MARKING (SOLID YELLOW)(4 INCH)	SF	224		\$0.00
50	630-	TRAFFIC CONTROL	LS	1		\$0.00
					Bid Total	\$0.00

Total Base Bid (written out):

Vendor Name:

Authorized Signature:

Print Name:

Phone Number:

Fax Number:

Email Address:

Date: